

SYNTHETIC DEMONSTRATION DOCUMENT - values are invented for the Wet Stack / Mireye prototype and are not real product or project data.

## AURORA DC-1 CAMPUS - MECHANICAL EQUIPMENT SCHEDULE

### Section 23 81 23 - Computer Room Air Handlers

#### CRAH-01

Nominal cooling capacity: 180 kW sensible

Entering water temperature: 18 degC

Leaving water temperature: 24 degC

Airflow: 12500 L/s

Supply voltage: 480 V

Full load amps: 32 A

Operating weight: 1120 kg

#### CRAH-02

Nominal cooling capacity: 180 kW sensible

Entering water temperature: 18 degC

Leaving water temperature: 24 degC

Airflow: 12500 L/s

Supply voltage: 480 V

Full load amps: 32 A

Operating weight: 1120 kg

#### CRAH-03 (redundant unit)

Nominal cooling capacity: 180 kW sensible

Operating weight: 1120 kg

#### GENERAL NOTES

All units certified to AHRI 1360. Ambient dry-bulb temperature at the outdoor condensing equipment shall not exceed 38 degC. Units shall maintain ASHRAE TC 9.9 Class A1 conditions in the white space.